



Todd Street Reconstruction
Water Street North to West End

Haddington Street Reconstruction
Dundas Street to Samuelson Street

Information Package

October 2020

Public Information Centre

Todd Street and Haddington Street Reconstruction
Public Information Centre
October 2020

What is the scope of work?

The City of Cambridge is proposing to reconstruct Todd Street from Water Street North to the West End and Haddington Street from Dundas Street to Samuelson Street.

Reconstruction will include

- Replacement of the existing watermain, appurtenances and services to property line
- Replacement of the existing sanitary sewer, appurtenances and services to property line
- Replacement of the existing storm sewer and appurtenances
- Replacement of the existing roadway, curb and gutter and sidewalk

Are there any changes proposed to the existing streetscape?

- Todd Street from Water Street North to the West End

Yes. The complete roadway including curbs and sidewalks will be reconstructed. The width of the existing asphalt surface is approximately 7.3m from Water Street North to the West End. The width of the existing sidewalks on the north and south sides of the road is approximately 1.2m. On the south side there is no sidewalk in front of the 3 westernmost properties.

The width of the proposed sidewalks on the north and south sides of the road will be increased to 1.5m as per the Accessibility for Ontarians with Disabilities Act (AODA). A 0.5m wide grass boulevard between concrete curb and sidewalk is proposed on both sides where sidewalk is proposed. The proposed sidewalks will be approximately in the same location as the existing sidewalks except they will be approximately 50mm closer to the property lines and they will be widened toward the road. The sidewalk on the north side will be extended at the west end to connect with the trail. No sidewalk is proposed on the south side in front of the 3 westernmost properties.

The width of the proposed asphalt will be increased to 7.8m from the existing 7.3m.

- Haddington Street from Dundas Street to Samuelson Street

Yes. The complete roadway including curbs and sidewalks will be reconstructed. The width of existing asphalt surface is approximately 6.6m from Dundas Street to Samuelson Street. The width of existing sidewalks on the north and south sides of the road is approximately 1.1m.

The width of proposed sidewalks on the north and south sides of the road will be increased to 1.5m as per the Accessibility for Ontarians with Disabilities Act (AODA). A 0.4m wide grass boulevard between concrete curb and sidewalk is proposed. The proposed sidewalks will be approximately in the same location as the existing sidewalks except they will be widened toward the road

The width of the proposed asphalt will be 6.6m, the same width as the existing asphalt.

Why is the City proceeding with this work?

The City of Cambridge upgrades infrastructure each year in order that aged facilities are replaced prior to there being a complete failure or the cost of maintenance becomes exorbitant. The existing watermain, storm sewers and sanitary sewers will be also replaced due to age and deterioration. All

service laterals will be replaced to the property line. Reconstruction of the road and concrete surface works is necessary due to deterioration and reconstruction of the underground services.

Can I upgrade my existing sanitary sewer and water service?

All water service laterals for single families will be replaced with 25mm diameter polyethylene pipe from the watermain to property line and all sanitary service laterals will be replaced with 100mm diameter PVC pipe from the sewer main to property line.

Any property owner wishing to have new (additional) or larger sized services must make written application to the City of Cambridge. Any new or upgrade service will be at the expense of the property owner making the request. Should you require a new or upgraded service, please contact Matt Holland of the Community Development Department at 519-623-1340 ext. 4751 so that your requirements can be incorporated as part of the construction.

Please note that the service installed would be to the property line only. Any work on private property would be the responsibility of the property owner who must obtain a permit under the Plumbing Code from the City's Building Department.

What is the timing of the reconstruction?

Construction is expected to take place in 2022 subject to budget approval.

Who will be doing the work?

A private contractor selected through the City's public tender process will undertake the work.

How will the reconstruction affect me?

During road reconstruction, it will be necessary to close the road to through traffic. Access to private property may be possible, but it will be at your own risk, as you will be traveling through a construction zone. For times you do not have access to your property, or if you do not wish to travel through the construction zone, alternate arrangements should be made for parking. Overnight parking will be permitted on intersecting streets within one block of the reconstruction but you must abide by all other existing parking restrictions (i.e. don't block a driveway, don't park too close to a fire hydrant, don't park where parking is prohibited, etc.).

How will pedestrian access be maintained?

To minimize disruption to pedestrians, the construction crew will:

- Maintain the existing sidewalk until its removal is absolutely necessary;
- Provide a temporary gravel sidewalk between removal of the old and placement of the new sidewalk;
- Whenever possible, provide advanced notice to the property owners and residents whose sidewalk or driveway will be temporarily affected

Will sanitary sewer and water services be interrupted?

Sewer and water service will be maintained throughout the duration of construction. However, short interruptions can be expected, particularly when the services to individual properties are transferred from existing mains to the new mains. In the majority of cases, interruptions will be limited to a few hours and will occur during normal working hours. Advance notification will be provided where

possible prior to any planned service interruption. During watermain reconstruction, a temporary above ground watermain may be installed. Each property will be connected from the temporary main to an outside water tap. Access onto your property will be required to provide the temporary connection.

How will disruptions be minimized?

One issue of critical importance to the City of Cambridge is to have the work completed while minimizing disruption to the neighbourhood. Road reconstruction and underground servicing is disruptive and at times will create noise, vibration due to compaction and a potential for dust. To address these disruptions, water and calcium chloride are used for dust control and construction activity is limited to daylight hours after 7:00 a.m.

Surface features existing on City property

On some reconstruction projects we find that residents have constructed gardens, shrubs, hedges, and fences within the City road allowance. If existing services are below that particular feature, there is a grade change or if the location of the sidewalk changes, you will be asked to relocate the garden, hedge etc onto your property prior to construction taking place.

When reconstructing the sidewalk, it may be necessary to cut back some driveways to match the new grade. If this is the case, the driveway will be saw-cut and a patch placed using the same material if possible. Impressed or coloured concrete driveways cannot be replaced to match the original, which is also the case with paving stone driveways (unless the owner has a supply of matching stones that the contractor could use).

If you have a sprinkler system installed along the edge of the roadway or sidewalk within the City's road allowance, please remove the piping prior to construction as the contractor will not be responsible for damage and the City will not replace it. You may have it reinstalled on private property after construction is completed if you wish.

Will blue box, green box and refuse collection be affected?

Blue box, green box and refuse collection will be maintained throughout the duration of construction. When access is restricted by construction operations, the construction crew will place the blue boxes and refuse containers at a location accessible by the collection service on collection days. To minimize problems during construction, it would be appreciated if all refuse is bagged – Yard Waste in paper bags, Household Garbage in plastic bags. **Please ensure that your address is clearly marked on containers/ blue boxes.**

How can I voice my comments?

The City of Cambridge realizes that reconstruction will cause inconvenience to the residents and businesses in the area and requests your cooperation, understanding and patience throughout its duration. Comments can be provided to the City through a number of avenues:

- City's online engagement platform (www.engagewr.ca/todd-haddington-reconstruction). Please note project plans will be **posted online only**, for a period of three weeks. The comment period will remain open during this three week period.
- A comment sheet is attached to this information package and you have the option to mail or e-mail this comment form to the undersigned.

In addition to your comments, other information we would like to receive from residents or institutions are your special needs, e.g. for disabled persons, water or sewer service improvements or driveway modifications. This written record will assist the City to address all the issues related to the reconstruction.

Information in an accessible format

If you require information in an accessible format or accommodation to access municipal services, please contact accessibility@cambridge.ca.

We thank you for reviewing this information package.

Matt Holland, P.Eng.
Project Engineer
Community Development
City of Cambridge
50 Dickson Street, P.O. Box 669
Cambridge, Ontario
N1R 5W8
Telephone 519-623-1340 ext 4751
Facsimile 519-740-7729
Email hollandm1@cambridge.ca

